

Date: Thursday, 2/9/2006 1:17:05 PM
 User: Kim Johnston

Process Sheet

Customer : CU-DAR001 Dart Helicopters Services	Drawing Name : SEAT FRAME ASSEMBLY
Job Number : 25790	
Estimate Number : 11122	
P.O. Number : N/A	Part Number : D3016041
This Issue : 2/9/2006 S.O. No. : N/A	Drawing Number : D3016 REV A
Prsht Rev. : NC	Project Number : N/A
First Issue : N/A Type : LARGE FAB ASSY	Drawing Revision : A
Previous Run : 25789	Material : N/A
Written By : SEE COMMENT Below	Due Date : 2/25/2006 Qty: 1 Um: Each
Checked & Approved By : <i>06.02.09</i>	
Comment : Est. A 01.09.19 New issue EC	

Additional Product

Job Number:



Seq. #:	Machine Or Operation:	Description :
----------------	------------------------------	----------------------

1.0	M4130NT0750W049	4130 Tube .750 OD x.049W
-----	-----------------	--------------------------



Comment: Qty.: 6.8250 f(s)/Unit Total : 6.8250 f(s)
 4130 Tube .750 OD x.049W
 Cut:- AISI 4130N tube, Ø3/4" x 0.049" wall
 Batch: ~~M11033~~ M10133

06/02/10

2.0	M4130NT1000W049	4130 Tube 1.0"D X .049"W
-----	-----------------	--------------------------



Comment: Qty.: 2.6250 f(s)/Unit Total : 2.6250 f(s)
 4130 Tube 1.0"D X .049"W *1.35W* Batch : M11591

06/02/10

3.0	M4130NT0500W049	4130 Tube .500 OD x.049W
-----	-----------------	--------------------------



Comment: Qty.: 4.2000 f(s)/Unit Total : 4.2000 f(s)
 4130 Tube .500 OD x.049W
 Cut- AISI 4130N tube, Ø1/2" x 0.049" wall
 Batch: M17109

06/02/10

4.0	D301617	Gusset
-----	---------	--------



Comment: Qty.: 1.0000 Each(s)/Unit Total : 1.0000 Each(s)

Gusset

Pick:

Qty	Part Number	Description	Batch
1	D3016-17	Gusset	B22066

06/02/10

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

Date: Thursday, 2/9/2006 1:17:06 PM
User: Kim Johnston

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: SEAT FRAME ASSEMBLY

Job Number: 25790

Part Number: D3016041

Job Number:



Seq. #:

Machine Or Operation:

Description :

5.0

D301613

Bracket



Comment: Qty.: 1.0000 Each(s)/Unit Total : 1.0000 Each(s)

Bracket

Pick:

Qty	Part Number	Description	Batch
1	D3016-13	Bracket	B16404

DD 06/02/10

6.0

D301615

Gusset



Comment: Qty.: 1.0000 Each(s)/Unit Total : 1.0000 Each(s)

Gusset

Pick:

Qty	Part Number	Description	Batch
1	D3016-15	Gusset	A16298

DD 06/02/10

7.0

D30201

Fitting



Comment: Qty.: 2.0000 Each(s)/Unit Total : 2.0000 Each(s)

Fitting

Pick:

Qty	Part Number	Description	Batch
2	D3020-1	Fitting	B22690

DD 06/02/10

8.0

QC5

INSPECT WORK TO CURRENT STEP



Comment: INSPECT WORK TO CURRENT STEP

DD 06-02-13

9.0

LARGE FAB 1

LARGE FABRICATION RESOURCE 1



Comment: LARGE FABRICATION RESOURCE 1

1-Cut all tubes as per Dwg D3016

2-Deburr

3-Weld as per Dwg D3016

A/R Steel Rod Batch: M9430

4-Transfer Drill Holes to D3016-041 From D3021-041

DD 06/02/13

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes ☐ No ☒ DQA: ☒ Date: 06/02/22
 QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

Date: Thursday, 2/9/2006 1:17:06 PM
User: Kim Johnston

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: SEAT FRAME ASSEMBLY

Job Number: 25790

Part Number: D3016041

Job Number:



Seq. #:

Machine Or Operation:

Description :

10.0

QC5/9

WELD INSPECTION



Comment: WELD INSPECTION

Weld as per Dwg D3016 using Welding Jig DT8597

PD 06-02-13

11.0

POWDER COATING

POWDER COATING



Comment: POWDER COATING

Install paint screws on fitting ends

Powder Coat Grey sandtex (Ref. 4.3.5.6) as per QSI 005

FC 06 02 21

12.0

QC3

INSPECT POWDER COAT/CHEMICAL CONVERSION



Comment: INSPECT POWDER COAT/CHEMICAL CONVERSION

SB 06/02/21

13.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

Identify and Stock

Location: GA

SB 06/02/21

14.0

DC

DOCUMENT CONTROL



Comment: DOCUMENT CONTROL

Inspection Level 21

DD 06/02/22 (1)

Job Completion



U 06-02-23

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries



DESIGN CP	DRAWN BY CP	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED #	APPROVED #	DRAWING NO. D3016	REV. A SHEET 1 OF 3
DATE 01.05.18		TITLE SEAT FRAME ASSEMBLY	SCALE NTS
A	01.05.18	NEW ISSUE	

QTY	PART NUMBER	DESCRIPTION	MATERIAL
X	D3016-041	SEAT FRAME ASSEMBLY	N/A
1	D3016-1	TUBE	AISI 4130N TUBE, Ø0.75 DIA x 0.049 WALL (M4130N-T0750W049)
2	D3016-3	TUBE	AISI 4130N TUBE, Ø0.75 DIA x 0.049 WALL (M4130N-T0750W049)
1	D3016-5	TUBE	AISI 4130N TUBE, Ø0.50 DIA x 0.049 WALL (M4130N-T0500W049)
2	D3016-7	TUBE	AISI 4130N TUBE, Ø0.50 DIA x 0.049 WALL (M4130N-T0500W049)
1	D3016-9	SADDLE	AISI 4130N TUBE, Ø1.00 DIA x 0.120 WALL (M4130N-T1000W120)
1	D3016-11	SADDLE	AISI 4130N TUBE, Ø1.00 DIA x 0.120 WALL (M4130N-T1000W120)
1	D3016-13	BRACKET	AISI 4130N SHEET, 18 GAUGE (M4130N-S049)
1	D3016-15	GUSSET	AISI 4130N SHEET, 18 GAUGE (M4130N-S049)
1	D3016-17	GUSSET	AISI 4130N SHEET, 18 GAUGE (M4130N-S049)
2	D3020-1	FITTING	N/A

NOTES

- 1) WELD PER DART QSI 004
- 2) ON SHEET METAL PARTS, BREAK ALL UNMARKED CORNERS 0.020-0.040
- 3) FINISH: POWDER COAT GREY SANDTEX (REF. 4.3.5.6) PER DART QSI 005 4.3
- 4) ALL DIMENSIONS ARE IN INCHES
- 5) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED





SHOP COPY
RETURN TO
ENGINEERING
UNCONTROLLED COPY
SUBJECT TO AMENDMENT
WITHOUT NOTICE
WORK ORDER
NO. 25790

RELEASED
01.05.30 #

Copyright © 2001 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.


D3016-041 SEAT FRAME ASSEMBLY











SHOP COPY
RETURN TO
ENGINEERING
UNCONTROLLED COPY
SUBJECT TO AMENDMENT
WITHOUT NOTICE
WORK ORDER
NO. 25790

RELEASED
01.05.18

COPYRIGHT © 2001 BY DART AEROSPACE LTD.		DESIGN UP	DRAWN BY UP	DART	DART AEROSPACE LTD. HARRISBURG, ONTARIO, CANADA
THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.		CHECKED #	APPROVED #		
		DATE 01.05.18	TITLE SEAT FRAME ASSEMBLY		SHEET 2 OF 3



NO. 25790
WORK ORDER
WITHOUT NOTICE
UNCONTROLLED COPY
SUBJECT TO AMENDMENT
SHOP COPY
RETURN TO
ENGINEERING



COPYRIGHT © 2001 BY DART AEROSPACE LTD.

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

DESIGN	CP	DRAWN BY	CP	DART	DART AEROSPACE LTD. HAWKESBURY, ONTARIO, CANADA
CHECKED	#	APPROVED	#	DRAWING NO. D3016	REV. A SHEET 3 OF 3
DATE	01.05.18	TITLE	SEAT FRAME ASSEMBLY	SCALE	1:2

RELEASED
9.05.30